

AD-A156 277


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
LIMESTONE DAM (HE 004... (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 81


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 277

FINAL

GEOTECHNICAL ENGINEERING (2)


SAINT JOHN RIVER BASIN
Limestone, Maine

LIMESTONE DAM ME 00492

PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM




DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
Waltham, Mass. 02154



DTIC FILE COPY

SEPTEMBER 1981



RECEIVED

SEP 10 1981

Contact: [illegible]

85 06 10 091

NATIONAL PROGRAM OF INSPECTION OF NON-FEDERAL DAMS
DRAFT REPORT REVIEW COMMENTS

Limestone

DAM, IDENTITY NO. MA 00192

GEOTECHNICAL ENGINEERING BRANCH

Page No.

Comments

1-1	Title 'NOYES BROOK DAM' is incorrect.
1-4	Elevation of streambed and top of dam indicate a dam height of 23 feet. The BA and Section 4, par. 1.2(L) list the dam height as 22 feet, which is correct?
BA, Sect 4.3 & Sect 7.3(C)	Conduct technical inspections every 2 years.
General	Should overall rating be 1 A/B, since the spillway capacity is inadequate?

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER ME 00492	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Limestone Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE September 1981
		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Saint John River Basin Limestone, Maine Limestone Stream		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is about 300 ft. long, 19 ft. high, and 9 ft. wide at the crest. The dam is rated fair because the spillway can not pass the test flood. It is small in size with a high hazard potential. No urgent or emergency actions are required for Limestone Community Dam based on this inspection.		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

LIMESTONE COMMUNITY DAM

ME 00492

ST. JOHN RIVER BASIN
LIMESTONE, MAINE

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Accession For		
NTIS GRA&I	<input checked="" type="checkbox"/>	
DTIC TAB	<input type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By _____		
Distribution/		
Availability Codes		
Avail and/or		
Dist	Special	
A/	23	ER



NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

Identification No. : ME 00492
Name of Dam : Limestone Community Dam
Town : Limestone
County & State : Aroostook, Maine
Stream : Limestone Stream
Date of Inspection : November 6, 1979

BRIEF ASSESSMENT


Limestone Community Dam is a dual purpose recreation and flood water retarding structure. It is an earthfill structure with a slurry wall cutoff trench. The spillway is a concrete paved, broad crested weir and chute that discharges into a stilling basin. The flow over the weir is uncontrolled. The embankment is approximately 300 feet long, 19 feet high and 9 feet wide at the crest. A 36" diameter low level outlet allows the reservoir to be drained to Elev. 516.5 NGVD. The normal depth of the reservoir is approximately 20 feet. A fishway is located immediately to the right of the spillway chute. The original earthfill embankment structure had a gabion and timber covered spillway which was damaged prior to 1977. Repair of the structure was designed and performed in 1977. That same year, heavy flows again washed out the gabion covered spillway. In 1978, a concrete slab spillway surface was designed and constructed to replace the former gabion covered spillway. A recreation pool is maintained behind the pool at Elev. 526.5.

The embankment dam, outlet works, central spillway chute, concrete training walls and fishway were found in good condition. In the earthfill embankment itself, there were no dips, sags or other evidence of distress. The concrete structures including the broad crested weir spillway were sound with no visible evidence of deterioration. The grass cover on the embankment was well established. The rip-rap on both the downstream and upstream faces was in good condition.

Based on a maximum storage of approximately 130 acre-feet and a height of 19 feet, Limestone Community Dam is classified as small. The dam's hazard classification has been established as high based on the potential for loss of more than a few lives in the event of a dam failure. The test flood was the 1/2 PMF and was estimated for the 27.9 square mile drainage area of rolling terrain using the "Preliminary Guidance for Estimating Maximum Probable Discharges in Phase I Safety Investigations", New England Division Corps of Engineers, March 1978. This yielded a peak inflow of 12890 cfs and a routed outflow of 12770 cfs. The

11
computed maximum reservoir level El. 536.2 was above the embankment crest El. 534 and overtopping of the embankment would occur.

No urgent or emergency actions are required for Limestone Community Dam based on this inspection. Remedial measures include developing a downstream warning system and conducting bi-annual technical inspections of the dam. It is also recommended that a second, more detailed hydrological study be performed on this dam to determine what effect flood routing through the two upstream dams would have on the performance of Limestone Community Dam.



J.E. Giles, Jr., P.E.

Project Manager

Massachusetts Registration No. 1643

11
CORPS OF ENGINEERS

SIGNATURE PAGE

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of Phase I investigation: however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

REPORT


1. PROJECT INFORMATION	
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
c. Scope of Inspection Program	1-1
1.2 Description of Project	1-2
a. Location	1-2
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-3
e. Ownership	1-3
f. Operator	1-3
g. Purpose of Dam	1-3
h. Design and Construction History	1-3
i. Normal Operational Procedure	1-3

<u>Section</u>	<u>Page</u>
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1
3. VISUAL INSPECTION	
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-1
d. Reservoir Area	3-2
e. Downstream Channel	3-2
3.2 Evaluation	3-2
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	4-1
a. General	4-1
b. Description of any Warning System in Effect	4-1
4.2 Maintenance Procedures	4-1
a. General	4-1
b. Operating Facilities	4-1
4.3 Evaluation	4-1
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General	5-1
5.2 Design Data	5-1

<u>Section</u>	<u>Page</u>
5.3 Experience Data	5-1
5.4 Test Flood Analysis	5-1
5.5 Dam Failure Analysis	5-1
6. EVALUATION OF STRUCTURAL STABILITY	6-1
6.1 Visual Observation	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-1
6.4 Seismic Stability	6-1
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
7.4 Alternatives	7-2


APPENDIXES

APPENDIX A - INSPECTION CHECKLIST	A-1
APPENDIX B - ENGINEERING DATA	B-1
APPENDIX C - PHOTOGRAPHS	C-1
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1



LIMESTONE COMMUNITY DAM
VIEW FROM BRIDGE BELOW DAM

Approx. 0.2 sq. mi. of Drainage Area not shown on map.



NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

LIMESTONE DAM, LIMESTONE MAINE

SECTION I

PROJECT INFORMATION

1.1 General

- a. Authority - Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Chas. T. Main, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Maine. Authorization and notice to proceed were issued to Chas. T. Main, Inc. under a letter of November 6, 1979 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0011 has been assigned by the Corps of Engineers for this work.
- b. Purpose
 - (1) The purposes of the inspection program are: To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
 - (2) To encourage and prepare the states to initiate effective dam safety programs for non-Federal dams.
 - (3) To update, verify and complete the National Inventory of Dams.
- c. Scope of Inspection Program - The scope of this Phase I inspection report includes:
 - (1) Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.

(2) A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.

(3) Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.

(4) An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgment on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.

1.2 Description of Project

- a. Location - The Limestone Community Dam is located on Limestone Stream in the Town of Limestone, Aroostook County, Maine. The dam location is included on U.S.G.S. 7.5 minute series Quadrangle, Limestone, Maine with approximate coordinates N46°45'45", W67°49'30".
- b. Description of Dam and Appurtenances - The project consists of three principal features: an earthfill dam, a spillway chute, and a fishway. The dam embankment is approximately 300 feet long and 19 feet high. The original dam had approximately the same dimensions. (Design and construction details of the original structure were not available.) The reconstructed structure used the original dam earthfill embankment and filled in the areas which had washed out with new fill. The fill materials are of glacial till origin with zoning limited to placing the more impervious material in the core and the more pervious material in the outside shells. The structure has an approximate 2' x 9' slurry trench below the core.

The spillway is an uncontrolled broad crested weir and chute with crest Elev. 526.5 NGVD. The spillway surface is a concrete slab. This concrete structure replaces the previous gabion covered spillway which was washed out during high flows. The upstream and downstream slopes at the spillway are approximately 1 vertical to 2.5 horizontal. The sides of the spillway are vertical reinforced concrete training walls. The adjacent left and right embankments are grass covered. The fishway runs adjacent to the right spillway training wall with gravel fill separating the two. The dam is equipped with a 36" RCP reservoir drain located to the right of the spillway. The drain is controlled by a sluice gate that operates inside the 6' diameter concrete riser on the right embankment.

Plans, profiles, and sections of the dam and its appurtenant structures are included in Appendix B. Photographs are shown in Appendix C.

- c. Size Classification - The maximum embankment height is 19 feet above the stream channel and the maximum storage is 140 acre feet at El. 534.0. This gives the dam a small size classification (since the storage is greater than 50 and less than 1,000 acre-feet) in accordance with the Recommended Guidelines for Safety Inspection of Dams.
- d. Hazard Classification - This facility is classified as a high hazard potential dam based on the potential for loss of more than a few lives in the event of a dam failure in eleven occupied dwellings downstream of the dam.
- e. Ownership - The dam and associated works are owned by the Town of Limestone, Maine.
- f. Operators - The project is designed for unsupervised operation. No manual operations are required to pass a flood flow. The project is operated and maintained by the Town of Limestone, Maine. The responsible person is Mr. Thomas Stevens, Town Manager, Limestone, Maine 04750, Telephone (207) 325-3131. (The Town Manager at the time of this inspection was Mr. Peerless J. Snow.)
- g. Purpose of Dam - The project is a flood water retarding and recreational facility. The reservoir drain intake sluice gate is currently closed and the reservoir maintained at El. 526.5 for fish and recreation purposes.
- h. Design and Construction History - Design and construction data concerning the original structure was not available. It is known that the original dam was similar to the existing structure except that it had wood timber training walls adjacent to the spillway and a combination of gabion/wood timber spillway surface rather than reinforced concrete. This dam was damaged during flood flows prior to 1977. The damage consisted primarily of a washout of the central spillway section. Rehabilitation of the structure was designed and performed in 1977 by Edward C. Jordan Company, Inc. from Presque Isle, Maine. During the same year the dam was again damaged by high flows. The following year, 1978, a federally assisted contract, "Rehabilitation of Community Dam, Heritage Conservation and Recreational Service, Project No. 23-00303" resulted in the present structure, completed in 1978. The design and repair work was by E.C. Jordan Co., Inc.
- i. Normal Operating Procedures - The reservoir is normally maintained at El. 526.5 for recreation purposes. All flood flows are passed through the spillway chute which is designed for uncontrolled discharge. No other operating procedures are in evidence.

1.3 Pertinent Data

a. Drainage Area - Limestone Community Dam controls a drainage area of 27.9 square miles. The watershed is approximately 65 percent wooded and 35 percent agricultural. There are two dams upstream; Noyes Brook Dam, D.A. of 2.85 square miles, and Durepo Brook Dam, D.A. of 20.03 square miles.

b. Discharge at Damsite

(1) Outlet Works - The spillway is a broad crested weir at elevation 526.5 with a reinforced concrete deck. The weir is 116 feet wide. A sluice gate and 36"Ø RCP provide the capability to drain the reservoir to El. 516.5.

(2) Maximum known flood - Unknown.

(3) Spillway capacity at top of dam - 7150 cfs @ El. 534.0.

(4) Spillway capacity at test flood elev. - 10550 cfs @ El. 536.2.

(5) Gated spillway capacity at normal pond elevation - N/A.

(6) Gated spillway capacity at test flood elevation - N/A.

(7) Total project discharge at top of dam - 7150 cfs @ El. 534.

(8) Total project discharge at test flood elevation - 12773 cfs @ El. 536.2.

c. Elevations (feet above NGVD)

(1) Streambed at toe of dam	515.0
(2) Bottom of cutoff	502.0
(3) Maximum tailwater	Not available
(4) Normal pool	526.5
(5) Full flood control pool	N/A
(6) Spillway crest	526.5
(7) Design surcharge (Original Design)	Not available
(8) Top of dam	534.0
(9) Test flood surcharge	536.2

d. Reservoir (Length in feet)

(1) Normal pool	1400
(2) Flood control pool	N/A
(3) Spillway crest pool	1400
(4) Top of dam	2900
(5) Test flood pool	3300

e. Storage (acre-feet)

(1) Normal pool	40
(2) Flood control pool	N/A
(3) Spillway crest pool	40
(4) Top of dam	142
(5) Test flood pool	207

f. Reservoir Surface (acres)

(1) Recreation pool	8
(2) Flood-control pool	N/A
(3) Spillway crest	8
(4) Test flood pool	34
(5) Top of dam	24

g. Dam

(1) Type	Earthfill
(2) Length	300 feet
(3) Height	19 feet
(4) Top Width	9 feet
(5) Side Slopes	Upstream 2.5 Hor. to 1 Vert. Downstream 2.5 Hor. to 1 Vert.

- | | |
|---------------------|------------------------------------|
| (6) Zoning | 2 zones |
| (7) Impervious Core | Most impervious
toward the core |
| (8) Cutoff | 2' x 9' slurry wall |
| (9) Grout curtain | N/A |
| (10) Other | N/A |

h. Diversion and Regulating Tunnel

- | | |
|---------------------------|-----|
| (1) Type | N/A |
| (2) Length | N/A |
| (3) Closure | N/A |
| (4) Access | N/A |
| (5) Regulating Facilities | N/A |

i. Spillway (Principal)

- (1) Type - Broad crested weir with reinforced concrete deck
- (2) Length of weir - 116 feet
- (3) Crest elevation - 526.5
- (4) Gates - N/A
- (5) U/S Channel - N/A
- (6) D/S Channel - Natural
- (7) General - Reinforced concrete vertical training walls
along both sides of spillway.

j. Regulating Outlets

- (1) Invert - El. 516.5
- (2) Size - 36" Dia. RCP
- (3) Description - Sluice gate to drain reservoir
- (4) Control Mechanism - 36" ϕ Sluice gate w/screw operator
- (5) Other - None

1.

SECTION 2
ENGINEERING DATA

2.1 Design

Information concerning the original design of the dam (prior to 1958) was unavailable. The reconstruction of the dam in 1977 was designed by the Edward C. Jordan Company, Inc., of Presque Isle, Maine. The latest rehabilitation of the structure (1978) was again designed by the E.C. Jordan Company. The design calculations used by this Company were unavailable to the inspection team. The construction drawings for both the "reconstruction" (1977) and "rehabilitation" (1978) were given to the inspection team by the Limestone Town Manager.

2.2 Construction

No construction records or photographs were available to the inspection team. A set of construction prints was reviewed. Those pertinent to this report are included in Appendix B. The drawings titled "Reconstruction of Community Dam" are those used for the earlier repair work (1977). The drawings titled "Rehabilitation of Community Dam" are those used for the later (existing) repair work (1978).

2.3 Operation

No formal operational procedures were available for review. The spillway is an uncontrolled structure requiring no manual operations.

2.4 Evaluation

- a. Availability: No design calculations were available to the inspection team. A set of General Contract Specifications for the latest repair work (1978) of the structure was reviewed.
- b. Adequacy: The lack of design calculations did not allow for a definitive review. Evaluation must be based on visual inspection, past performance history, and sound engineering judgment and experience.
- c. Validity: The limited data available restrict evaluation of the Limestone Community Dam and appurtenances to the visual inspection and sound engineering judgment. The field inspection indicated that the external features of Limestone Community Dam substantially agree with those shown on the available plans.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General - The field inspection was conducted by L. Seward and J. Jonas of Chas. T. Main, Inc. on 6 November 1979, and J. E. Giles, Jr. on August 12, 1981. On the date of inspection, the Limestone Community dam and appurtenances were in good condition. No urgent or emergency actions are required at this time.

b. Dam

(1) Crest - The embankment crest was true to line with no apparent dips, sags, cracks or other evidence of distress (Photo 6). The as-built camber was observed and appears unchanged. The crest is grass covered with no pavement.

(2) Upstream slopes - The upstream slope riprap appeared in good condition. The slopes above the normal pool El. 526.5 have a well developed tight grass cover (Photo 4). There was no evidence of sloughing or erosion on the slopes.

(3) Downstream slopes - The downstream slope rip-rap appeared in good condition. The slopes have well developed, tight grass covers. No significant gully action was observed on the slopes (Photos 5 and 6). No slides or sags were observed.

(4) Downstream toe - The downstream toe is generally dry with no boils or seeps observed.

(5) Underdrain system - None.

(6) Instrumentation - No instrumentation was observed.

c. Appurtenant Structures

(1) Spillway - The broad crested weir spillway and chute were in good condition (Photo 5). The adjacent reinforced concrete training walls were also in good shape with no visible deterioration.

(2) Fishway - The fishway appeared in good condition. The downstream fishway inlet is located on the right side of the spillway chute.

(3) The outlet works were not accessible. The visible portion of the circular concrete riser appeared in good condition.

d. Reservoir Area - No areas of potential or actual shoreline movement were observed (Photo 3).

e. Downstream Channel - Approximately 200 yards downstream, Limestone Stream flows under Highway 229. The opening in the bridge is approximately 7' x 29'.

3.2 Evaluation - In general, the dam and appurtenances are in good condition. The short abutment slopes are stable and in good shape. The concrete structures are sound. No urgent or emergency repairs are required.

SECTION 4

OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

- a. General: The spillway is an uncontrolled crest structure. No manual operations are required to insure safe passage of a flood flow. No recent operation of the reservoir drain is reported.
- b. Description of Downstream Warning System: No warning system or emergency evacuation plans are in effect for this project.

4.2 Maintenance Procedures

- a. General: No regular maintenance procedures are in effect for this project.
- b. Operating Facilities: There are no manual operating facilities at this structure except for the reservoir drain gate. No regular maintenance procedures for the project operating facilities are specified.

4.3 Evaluation

The operating and maintenance procedures are limited for this project. The owner should establish procedures to inspect the structures regularly, to continue to keep the embankment free of brush and trees, and to monitor the level of the reservoir during periods of intense rainfall.

The owner should arrange to have a technical inspection made on a bi-annual basis. The owner should establish a downstream warning system to follow in the event of emergency conditions.

SECTION 5

EVALUATION OF HYDROLOGIC AND HYDRAULIC FEATURES

- 5.1 General - The watershed is 27.9 square miles of rolling terrain. The dam is located on the Limestone Stream in the Town of Limestone. The earth embankment develops sufficient storage to reduce the peak from 12890 cfs to 12773 cfs (about 1% reduction). The Durepo Brook (D.A. of 20 sq. mi) and the Noyes Brook (D.A. of 3 sq. mi.) Dams are inside the drainage area of the Limestone Community Dam, and they are part of the S.C.S. Limestone Watershed Work Plan.
- 5.2 Design Data - The dam was designed and constructed by the Edward C. Jordan Company Inc. from Presque Isle, Maine. The concrete section of the dam is in the form of a broad crested weir with a width of 116 feet and a crest elevation of 526.5 feet. The channel sides are formed by the vertical concrete walls that extend to Elev. 534. The dam embankment has the same top elevation of 534 feet. The reservoir drain system consists of a six foot diameter precast concrete riser with a reservoir drain inlet of reinforced concrete located about 300 feet upstream of the dam, a 36 inch inlet pipe with an invert elevation of 516.5 feet and an outlet downstream of the spillway apron. The upstream and downstream slopes of the spillway are approximately 1 vertical to 2.5 horizontal.
- 5.3 Experience Data - It is known that heavy flows in the past have seriously damaged the dam at least twice; once prior to 1977 and once in 1977. The magnitude of these flows was unavailable.
- 5.4 Test Flood Analysis - Based upon "Preliminary Guidance for Estimating Maximum Probable Discharge", dated March 1978, the watershed classification (rolling), the PMF is estimated to be equivalent to 25,770 cfs. (921 csm). For this portion of Maine the Maximum Probable Runoff is assumed to be 13 inches. Upstream, the Durepo Brook and the Noyes Brook reservoirs control more than 80 percent of the drainage area. By considering the flood reducing effects of these reservoirs the test flood for this high hazard, small size dam is selected to be equivalent to the 1/2 PMF or 12,890 cfs (460 csm).

In our hydraulic computations, the flood routing starting elevation was the spillway crest elevation 526.5 NGVD. The routed test flood outflow was determined in accordance with Corps of Engineers "Guidance for Estimating Effect of Surge Storage on Maximum Probable Discharges", and the hydraulic characteristics of the dam. Spillway discharge was computed as flow over a weir. The routed test flood outflow was determined to be approximately 12770 cfs, (about one percent reduction), and corresponding water surface elevation 536.2 ft. The top of the dam is at elevation 534.0 ft and thus the dam would be overtopped by 2.2 ft. The spillway capacity of 7150 cfs is about 56 percent of the test flood.

Another test flood equivalent to 1/4 PMF (6442 cfs) was routed through the reservoir and the outflow was calculated to be 6410 cfs, 90 percent of the spillway capacity and no overtopping occurred.

- 5.5 Dam Failure Analysis - The dam failure was assessed using the "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs" prepared by the Corps of Engineers. The reservoir water level was assumed at the top of the dam prior to the breach event. The flooding damage was first analyzed for prefailure condition by considering a discharge from the dam equal to the spillway capacity, 7150 cfs. The water depths in the river due to this flood were calculated to be approximately 11 feet. About 14 houses 500-1000 feet downstream are located 5 to 10 feet above the stream bed. These houses and the bridge on the road of 229 will be damaged during this prefailure flood.

The additional flood discharge due to breaching of the dam was calculated to be 15600 cfs. In these calculations the reservoir volume prior to failure is 142 ac-ft, the breach height is 19 ft, and the breach width is 112 ft. Immediately downstream after the failure the total discharge becomes 22750 cfs with a depth of 16.8 ft. In this case the spillway becomes submerged and the decrease of its discharge is estimated to be 6 percent. The new spillway discharge of 6718 cfs together with routed breach discharges was considered in calculating the downstream water depths. The calculations (see Appendix D) showed that water depths will be 15.9 - 15.3 ft. and an additional 3 houses (previously unflooded) located 500 - 100 ft. downstream will be impacted by approximately 5-7 feet of water.

A second breach study was performed to evaluate the failure effect in dry conditions. In this case water levels were assumed at spillway crest elevation. The height of the breach was 11.5 ft. and the width 170 ft. The breach discharge was 3900 cfs. This was routed downstream. The calculations results show that about 11 houses will be flooded with water to depths of approximately three feet.

From these studies it is concluded that this dam should be classified as having a high hazard potential because more than a few lives could be lost in the event of a dam breach. Furthermore, it is shown that about fourteen homes are presently located in the flood plain area and will be damaged during a breach event.

SECTION 6

EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observation

The visual inspection of November 6, 1979 revealed no dips, sags, depressions or other evidence of instability. Nothing was noted that would indicate that the dam structure is unstable.

6.2 Design and Construction Data

Design calculations and construction records were not available for review in preparing this report. The construction drawings for the dam repair work were reviewed.

6.3 Post Construction Changes

No evidence of modification to the dam since the rehabilitation of the dam in 1978 was observed.

6.4 Seismic Stability

The dam is located in Seismic Zone No. 2 and, in accordance with recommended Phase I guidelines, does not warrant seismic analysis.

SECTION 7

ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

- a. Condition - This inspection indicates that the Limestone Community Dam is in good condition. The inspection revealed the following:
 - (1) There are approximately fourteen homes located in the flood plain immediately downstream. These will be damaged by a flow equal to the capacity of the spillway (or when the water level is at the top of the dam).
 - (2) The spillway capacity is 7150 cfs which is approximately 56 percent of the Test Flood outflow (1/2 PMF).
 - (3) The appearance of the concrete spillway and adjacent earthfill embankments is good.
- b. Adequacy of Information - The lack of in-depth engineering data did not allow for a definitive review of this dam. Therefore, the adequacy of the dam could not be assessed from the standpoint of reviewing design and construction data but is based solely on visual inspection and engineering judgment.
- c. Urgency - The remedial measures presented below should be implemented by the Owner within one year of receipt of this Report.

7.2 Recommendations

1. Because of the location of this dam in a densely populated area and the results of the Dam Failure Analyses it is recommended that a second, more detailed hydrological study be performed for this dam. This study should take into consideration the reducing effects of the upstream (Durepo Brook and Noyes Brook) dams during flood flows as well as the effect that the Route 229 bridge immediately downstream will have.
2. It is also recommended that the homes or businesses located on the flood plain immediately downstream be relocated.

7.3 Remedial Measures The owner should:

- a. Develop a downstream warning plan to be used in the event of an emergency at the dam.
- b. Establish a system to monitor the project during periods of intense rainfall.

- c. Implement a monthly visual inspection program of the dam and appurtenances. Observations should be recorded in a maintenance log.
- d. Conduct bi-annual technical investigations of the project.
- e. Establish regular maintenance procedures and continue to keep the embankments well-groomed and free of brush and trees.
- f. Insure the operability of the reservoir drain.
- g. Obtain and maintain a readily accessible set of as-built drawings and technical investigation reports.

APPENDIX A

FIELD INSPECTION CHECK LIST

PROJECT Limestone Community Dam

TIME 9:30

U.S. ELEV. U.S. DN.S.

1. <u>Lewis B. Seward - Hydrologist</u>	6. _____
2. <u>Jonas N. Jonas - Civil Engineer</u>	7. _____
3. <u>Peerless J. Snow - Limestone Town Manager</u>	8. _____
4. <u>J. E. Giles, Jr. - Project Manager*</u>	9. _____
5. _____	10. _____

INSPECTED BY	REMARKS

1. All of the project features were inspected by each of the party members.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.
- 10.

INSPECTION CHECKLIST

PROJECT Limestone Community Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill dam w/concrete spillway NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	534
Current Pool Elevation	527
Maximum Impoundment to Date	Not available
Surface Cracks	none visible
Pavement Condition	grassed and riprap at water line
Movement or Settlement of Crest	not noticeable
Lateral Movement	not noticed
Vertical Alignment	not noticed
Horizontal Alignment	good
Condition at Abutment and at Concrete Structures	very good - earthfill and riprap
Indications of Movement of Structural Items on Slopes	none visible
Trespassing on Slopes	none
Vegetation on Slopes	thick grass, not mowed
Sloughing or Erosion of Slopes or Abutments	none -
Rock Slope Protection - Riprap Failures	riprap at concrete intake walls-good condition
Unusual Movement or Cracking at or near Toes	none noticed
Unusual Embankment or Downstream Seepage	none
Piping or Boils	none
Foundation Drainage Features	2-in pipe relieving ports at toe of concrete spillway
Toe Drains	see above
Instrumentation System	none

INSPECTION CHECKLIST

PROJECT Limestone Community Dam

DATE Nov. 8, 1979

PROJECT FEATURE Earthfill dam in concrete spillway

NAME Lewis B. Seward

DISCIPLINE _____

NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. <u>Approach Channel</u> Slope Conditions Bottom Conditions Rock Slides or Falls Log Boom Debris Condition of Concrete Lining Drains or Weep Holes	Not applicable
b. <u>Intake Structure</u> Condition of Concrete Stop Logs and Slots	New precast pipe Not applicable

INSPECTION CHECKLIST

PROJECT Limestone Community Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill dam w/concrete NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. <u>Concrete and Structural</u>	
General Condition	very good
Condition of Joints	tight
Spalling	none
Visible Reinforcing	none
Rustiny or Staining of Concrete	none
Any Seepage or Efflorescene	none
Joint Alignment	good
Unusual Seepage or Leaks in Gate Chamber	gate shaft was not accessible
Cracks	none
Rusting or Corrosion of Steel	none
b. <u>Mechanical and Electrical</u>	
Air Vents	none
Float Wells	none
Crane Hoist	none
Elevator	none
Hydraulic System	none
Service Gates	none
Emergency Gates	manually operated gate valve
Lightning Protection System	none
Emergency Power System	none
Wiring and Lighting System in Gate Chamber	none

INSPECTION CHECKLIST

PROJECT Limestone Community Dam DATE Nov. 8, 1979
PROJECT FEATURE Earthfill dam in concrete NAME Lewis B. Seward
spillway NAME Jan N. Jonas
DISCIPLINE _____

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - TRANSITION AND CON- DUIT</u> General Condition of Concrete Rust or Staining on Concrete Spalling Erosion or Cavitation Cracking Alignment of Monoliths Alignment of Joints Numbering of Monoliths	Concrete pipe buried under dam embankment - not accessible for inspection.

INSPECTION CHECKLIST

PROJECT Limestone Community Dam DATE Nov. 8, 1979
PROJECT FEATURE Earthfill dam w/concrete spillway NAME Lewis B. Seward
DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	precast concrete pipe w/riprap
Rust or Staining	none
Spalling	none
Erosion or Cavitation	none
Visible Reinforcing	none
Any Seepage or Efflorescence	none
Condition at Joints	good, tight joints
Drain Holes	none visible
Channel	
Loose Rock or Trees Overhanging Channel	none
Condition of Discharge Channel	grassed slopes w/riprap

INSPECTION CHECKLIST

PROJECT Limestone Community Dam

DATE Nov. 8, 1979

PROJECT FEATURE Earthfill Dam w/concrete spillway

NAME Lewis B. Seward

DISCIPLINE _____

NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p> <p>a. <u>Approach Channel</u></p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Approach Channel</p> <p>b. <u>Weir and Training Walls</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Any Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Drain Holes</p> <p>c. <u>Discharge Channel</u></p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Channel</p> <p>Other Obstructions</p>	<p>spillway located in the middle of dam</p> <p>new concrete - very good</p> <p>none</p> <p>none</p> <p>none</p> <p>none</p> <p>none</p> <p>none</p> <p>natural river channel</p> <p>good</p> <p>none</p> <p>none</p> <p>rocky</p> <p>none</p>

INSPECTION CHECKLIST

PROJECT Limestone Community Dam

DATE Nov. 8, 1979

PROJECT FEATURE Earthfill dam w/concrete
spillway

NAME Lewis B. Seward

DISCIPLINE Hydro

NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SERVICE BRIDGE</u> a. <u>Super Structure</u> Bearings Anchor Bolts Bridge Seat Longitudinal Members Under Side of Deck Secondary Bracing Deck Drainage System Railings Expansion Joints Paint b. <u>Abutment & Piers</u> General Condition of Concrete Alignment of Abutment Approach to Bridge Condition of Seat & Backwall	Not applicable

1/

APPENDIX B
ENGINEERING DATA

- Note: 1. All design records are in storage at the:
National Archives and Records Service
GSA Federal Archives and Records Center
380 Trapelo Road, Waltham, Massachusetts 02154
617-223-2657
2. No past inspection reports were available for
review or are known to exist.

LIST OF ENCLOSED DRAWINGS

A. "Rehabilitation of Community Dam," Project No. 20131.

	<u>Drawing Number</u>
<u>1.</u> Existing Structure and Site Preparation	C-100 Sheet 1 of 8
<u>2.</u> Concrete Sections	C-102 Sheet 3 of 8
<u>3.</u> Sections	C-300 Sheet 4 of 8


B. "Reconstruction of Community Dam," Project No. 7409963 E.

	<u>Sheet Number</u>
<u>4.</u> Existing Site and Exploration Plan	1
<u>5.</u> Dam and Swimming Area Plan	7
<u>6.</u> Dam Profile and Gabion Plan View	8
<u>7.</u> Dam Cross Section	10
<u>8.</u> Subsurface Geologic Profile	16

References

Material from the following references was extracted and incorporated herein:


- a. "Limestone Stream Watershed Work Plan" Central Aroostook Soil Conservation District December, 1964.
- b. Limestone Community Dam Construction Drawings: "Rehabilitation of Community Dam" (8 sheets), 1978 and also "Reconstruction of Community Dam" (21 sheets), 1976.
- c. "Durepo Brook - Invitation to Bid" March 1971 SCS construction specification (Typ.)
- d. SCS Technical Information Storage and Retrieval System Printout.



- NOTES:**
- 1) TIMBER SPILLWAY AND CUT-OUT RAFF SHALL BE REMOVED.
 - 2) THE ENGINEER IN THE FIELD WILL DETERMINE THE NUMBER OF GABIONS TO BE REMOVED.
 - 3) IN AREAS WHERE SETTLEMENT OF GABIONS HAS OCCURRED, AREAS DESIGNATED ON THE PLANS OF THE ENGINEER, THE GABIONS SHALL BE REMOVED AND THE Voids Filled WITH MATERIAL CONFORMING TO SECTION 2.01 AND AS SPECIFIED IN THE SPECIFICATIONS. THE VOIDS SHALL BE FILLED UP TO THE BOTTOM ELEVATION OF THE GABIONS. THE GABION STIFF FILL SHALL BE REPLACED.
 - 4) WHERE GABIONS ARE NOT TO BE REMOVED, CONCRETE SHALL BE PLACED ON THE GABIONS AFTER LEVELING (COMBING) WITH ZONE II MATERIAL.
 - 5) IF THE GABIONS ARE REMOVED, THE POND DRAIN SHALL BE REMOVED BY THE ENGINEER AND REMOVED A MINOR.
 - 6) A DRAINAGE DITCH 10 FEET OR THE DRAINAGE END AND 10 FEET OR THE DOWNSTREAM END OF THE POND SHALL BE REMOVED. THE REMAINDER SHALL BE COMPLETELY REMOVED WITH CONCRETE AND SAVED AT BOTH ENDS. CONTRACTOR SHALL SUBMIT A PLAN FOR FILLING AND SEALING THE PORTION OF THE PIPE TO REMAIN FOR REVIEW BY THE ENGINEER PRIOR TO STARTING THE WORK.

NO.	REFERENCE	REV.	DATE	STATUS	MF BY
		1	7/4/78	FOR CONSTRUCTION	
		2		REBUILT FOR BID	
		3			
		4			
		5			
		6			
		7			
		8			
		9			
		10			
		11			
		12			
		13			
		14			
		15			
		16			
		17			
		18			
		19			
		20			
		21			
		22			
		23			
		24			
		25			
		26			
		27			
		28			
		29			
		30			
		31			
		32			
		33			
		34			
		35			
		36			
		37			
		38			
		39			
		40			
		41			
		42			
		43			
		44			
		45			
		46			
		47			
		48			
		49			
		50			
		51			
		52			
		53			
		54			
		55			
		56			
		57			
		58			
		59			
		60			
		61			
		62			
		63			
		64			
		65			
		66			
		67			
		68			
		69			
		70			
		71			
		72			
		73			
		74			
		75			
		76			
		77			
		78			
		79			
		80			
		81			
		82			
		83			
		84			
		85			
		86			
		87			
		88			
		89			
		90			
		91			
		92			
		93			
		94			
		95			
		96			
		97			
		98			
		99			
		100			


173



HERITAGE CONSERVATION & RECREATION S
PROJECT NO 23-00303

BY CHITAPPE		 EDWARD C. JORDAN CO., INC. ENGINEERING · PLANNING · ARCHITECTURE PORTLAND BANGOR PORTSMOUTH ISLE, MAINE	DRAWN <i>BEW</i> 7-14-70 CHECKED <i>GOC</i> DATE	TITLE REHABILITATION OF COMMUNITY DAM
		TOWN OF LIMESTONE LIMESTONE, MAINE	PROJECT NO 23-00303 DATE 7-14-70 SCALE 1" = 10'	EXISTING STRUCTURE SITE PREPARATION 20131 C-10C SHT 1

283



HERITAGE CONSERVATION & RECREATION SERVICE
PROJECT NO 23-00303


JORDAN CO., INC. PLANNING ARCHITECTURE FOR PRESQUE ISLE, MAINE	DESIGNER G.O.C.	DATE 2-11-78	REHABILITATION OF COMMUNITY DAM	
	PROJECT NO 2718-78	DATE 27-10-78	EXISTING STRUCTURE & SITE PREPARATION	
LIMESTONE E. MAINE	SCALE 1" = 10'	PROJECT NO 20131	C-100 SHT. 1 OF 8	

2013


[illegible]


101.5

REPRODUCED AT GOVERNMENT EXPENSE



HERITAGE CONSERVATION RECREATION
PROJECT N. 23 - 3.

 EDWARD C. JORDAN CO., INC. ENGINEERING PLANNING ARCHITECTURE PORTLAND BANGOR PRESQUE ISLE, MAINE	DESIGN: <i>HCJ</i> DRAWN: <i>ROC</i> CHECKED: <i>ROC</i> DATE: <i>7/1/78</i> PROJECT: <i>00101</i> SHEET: <i>2</i> SCALE: <i>1" = 10'</i>	REHABILITATION COMMUNITY GENERAL PL	
	TOWN OF LIMESTONE LIMESTONE, MAINE	PROJECT NO. <i>00101</i> SHEET NO. <i>2</i>	C101 SHEET 2
	MP BY <i>CH/APP</i>	SCALE: <i>1" = 10'</i>	C101 SHEET 2
	283	283	283



HERITAGE CONSERVATION RECREATION SERVICE
PROJECT N. 23 & 33

C. JORDAN CO., INC.

PLANNING ARCHITECTURE
BANGOR PRESQUE ISLE MAINE

LIMESTONE
TONE, MAINE

DESIGN	2/1/8
DRAWN	J.F.S.
CHECKED	7/14/8
APPROVED	
PROJECT NO.	
DATE	7/14/8
SCALE	1" = 10'


REHABILITATION OF
COMMUNITY DAM

GENERAL PLAN


20131

C101 SHEET 2 OF 5

393






ELEVATION EAST WALL
(LOOKING EAST)
SCALE 1/8"=1'-0"



ELEVATION WEST WALL
(LOOKING WEST)
SCALE: 1/4" = 1'-0"


HERITAGE CONSERVATION &
PROJECT NO :

	EDWARD C. JORDAN CO., INC. ENGINEERING · PLANNING · ARCHITECTURE PORTLAND · BANGOR · PRESQUE ISLE, MAINE		OWNER <i>KCMC</i> DRAWN <i>G.A. Puro</i> DATE SHEET NO. PROJECT <i>W. H. 78</i> REV. NOS. CLASS SCALE <i>AS NOTED</i>	TITLE REHAE COMI CONCRE SHEET NO. DATE NO.
	TOWN OF LIMESTONE LIMESTONE, MAINE			



NO.	REVISION	DATE	BY	STATUS	APP. BY
0	FOR CONSTRUCTION				
1	7/8/78			CON'L. REVISION	
2	7/8/78			ISSUED FOR BIDS	

REPRODUCED AT GOVERNMENT EXPENSE



HERITAGE CONSERVATION & RECREATION SERVICE
PROJECT NO 23-00303

HARD C. JORDAN CO., INC.

ENGINEERING - PLANNING - ARCHITECTURE
PORTLAND BANGOR PRESQUE ISLE, MAINE

TOWN OF LIMESTONE
LIMESTONE, MAINE

DESIGNED BY	W. C. JORDAN	DATE	7/1/77
CHECKED BY	H. A. P. P.	DATE	8/1/77
APPROVED BY		DATE	
REVISIONS			
NO.	DESCRIPTION	DATE	
1	AS NOTED		


REHABILITATION OF
COMMUNITY DAM

CONCRETE SECTIONS




20131

C 102 SHT 3 OF 8

393





NO.	DATE	DESCRIPTION	BY	CHKD.	STATUS	REV. BY
1	7/8/78	FOR CONSTRUCTION				
2	7/8/78	CON'L REVISION				
3	7/14/78	ISSUED FOR BIDS				



HERITAGE CONSERVATION PROJECT NO.	
EDWARD C. JORDAN CO., INC. ENGINEERING PLANNING ARCHITECTURE PORTLAND BANGOR PRESQUE ISLE, MAINE	REHA CON
TOWN OF LIMESTONE LIMESTONE, MAINE	C-300

2083



HERITAGE CONSERVATION & RECREATION SERVICE
PROJECT NO 23-00303

RD C. JORDAN CO., INC.

OFFERING PLANNING ARCHITECTURE
LAND BANGOR PRESQUE ISLE, MAINE

OFFICE OF LESTONE
LESTONE, MAINE


DATE	7/1/78
DESIGNED BY	7/4/78
CHECKED BY	
APPROVED BY	07/14/78
SCALE	4" = 1'-0"


REHABILITATION OF
COMMUNITY DAM

SECTIONS


20131
C-300 SHEET 4 OF 8

11V
D





				REGION	PC	BLK 100	TOWN OF LIMESTONE LIMESTONE, MAINE	PROJECT RECON COM 1
				BLK 100	APP			
				BLK 100			Jordan Gornill Associates Geotechnical Consultants	TITLE EXIS EXPL
				APP				
				APP			PORTLAND, BARRON AND PORTER ISLE, MAINE	DATE 11-15-50
				APP				
DATE	BY	STATUS	APP	APP	W. B.			




LEGEND -


- EXISTING CONTOUR
- PROPERTY LINE
- - - SANITARY SEWER
- MANHOLE
- BON. PIN
- MONUMENT
- - - GUARDRAIL
- ◆ BORING (M.T.B.)
- HAND SOUNDING (M.T.B.)
- 1/2" APPROX. DEPTH OF WALK

DATE	6/6	PROJECT	TOWN OF LIMESTONE LIMESTONE, MAINE	CLIENT	RECONSTRUCTION OF COMMUNITY DAM	SHEET NO.	1
BY	JTP						
CHECKED		DESIGNED	Jordan Gorrell Associates Geotechnical Consultants	TITLE	EXISTING SITE / EXPLORATION PLAN	SCALE	1"=50'
APP'D							
APP'D		PORTLAND, BANGOR AND PRESQUE ISLE, MAINE	7409963C	DATE	6/6		

333



1313




NOTE:
ALL DISTANCES ARE
GIVEN IN FEET AND
ALL ANGLES IN DEGREES

LEGEND

- EXISTING CON.
- EXISTING SPOT
- EXISTING FENC.
- APPROX. EXISTING
- FINISH CONTOUR
- TOP OF DAM LIA.
- WOOD CRIB OVER
- RIP-RAP 2' DE
- STONE FILL 1'
- SAND BEACH 12'
- BORING LOCATION
- SLOPE INDICATOR
- POND DRAIN
- FISHWAY
- CRUSHED ROCK


						DESIGNED BY	JMS	CLIENT	TOWN OF LIMESTONE LIMESTONE, MAINE	PROJECT	RECONSTRUCTION COMMUNITY DAM
						CHECKED BY	AMP/DM				
						DATE	9/20				
						APPROVED BY			EDWARD C. JORDAN CO., INC.	TITLE	DAM & SW/MAIN PLAN
						DATE	9/20		ENGINEERING, PLANNING, ARCHITECTURE HYDROLOG., DRAINAGE, AND PRESERVE ISLS., MAINE	SCALE	AS SHOWN
REV	DATE	BY				STATUS		APPROVED BY	DATE	APPROVED BY	DATE




373

7+00


8+00



GABION PLAN




DAM PROFILE



11.3

8.00


9.00



GABION PLAN VIEW

LEGEND:

- 3' x 6' Gabion 12' Deep
- 3' x 8' Gabion 12' Deep
- 3' x 12' Gabion 12' Deep
- 3' x 9' Gabion 18' Deep



PROFILE





REV	DATE	BY	STATUS	APPD	APPD	DESIGN	CHK	CLIENT	PROJECT
								TOWN OF LIMESTONE	RECC
								LIMESTONE, MAINE	COM
1.0	1/1/76	AG ADVERTISED		APPD	CHKD			EDWARD C. JORDAN CO., INC.	TITLE
2.0	8/24/76	AS SUBMITTED FOR REVIEW		APPD				ENGINEERING, PLANNING, ARCHITECTURE	GAB
								PORTLAND, MAINE, AND PREQUEP ISLE, MAINE	SCALE 1"

203

REPRODUCED AT GOVERNMENT EXPENSE

2.00

LEGEND:

-  3x6 Gabion 12' Deep
-  3x9 Gabion 12' Deep
-  3x12 Gabion 12' Deep
-  5x9 Gabion 8' Deep

545

540

535

530

525

520

515

510

505


500

INDICATES BORINGS 50% SPACING MIN. AT
OFFSET FROM BASELINE SEE SHEET FOR LOCATION

2.00


DESIGNED BY	SR	CLIENT	TOWN OF LIMESTONE LIMESTONE, MAINE	PROJECT	RECONSTRUCTION OF COMMUNITY DAM	SHEET NO.	8
DRAWN BY	SR					DRAWING NO.	
CHECKED BY	SR						
DATE	02/25	ENGINEER	EDWARD C. JORDAN CO., INC.	TITLE	DAM PROFILE GABION PLAN VIEW		
REVIEW	SR		ENGINEERING, PLANNING, ARCHITECTURE	SCALE	1"=20'	REV NO.	
STATUS	APPD		PORTLAND, MAINE AND PRESQUE ISLE, MAINE				

3033







243



3083




K-E
NATIONAL BUREAU OF
MINES & GEOLOGICAL SURVEY





APPENDIX C

PHOTOGRAPHS






PHOTO #1
VIEW FROM LEFT
BANK ACROSS OLD
HIGHWAY 165



PHOTO #2
VIEW FROM LEFT BANK
ACROSS OLD HIGHWAY
165



PHOTO #3
UPSTREAM VIEW OF
RESERVOIR WITH NEW
HIGHWAY 165



PHOTO #4
RIGHT ABUTMENT WITH
ROCKFILL DAM AND
VALVE SHAFT



PHOTO #5
SPILLWAY WITH FISH
LADDER AND VALVE
SHAFT




PHOTO #6
OUTLET PIPE (36")
FISH LADDER WITH
RETAINING WALL AND
SPILLWAY



PHOTO #7

VIEW UPSTREAM FROM


BELOW HIGHWAY 229

BRIDGE

APPENDIX D

HYDROLOGIC & HYDRAULIC COMPUTATIONS

ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow (Q_{p1}) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " Q_{p1} ".

b. Determine Volume of Surcharge ($STOR_1$) In Inches of Runoff.


c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$

STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " Q_{p2} "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " Q_{p3} ".

"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40' OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_0 = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS 1/2 OF S , SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2} (\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING Q_{p2} (TRIAL).

D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_1 + V_2}{2S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

SURCHARGE STORAGE ROUTING SUPPLEMENT

STEP 3: a. Determine Surcharge Height and
"STOR₂" To Pass "Q_{p2}"

b. Avg "STOR₁" and "STOR₂" and
Compute "Q_{p3}".

c. If Surcharge Height for Q_{p3} and
"STOR_{AVG}" agree O.K. If Not:

STEP 4: a. Determine Surcharge Height and
"STOR₃" To Pass "Q_{p3}"

b. Avg. "Old STOR_{AVG}" and "STOR₃"
and Compute "Q_{p4}"


c. Surcharge Height for Q_{p4} and
"New STOR_{AVG}" should Agree
closely

MAIN

Client ORR & ENGINEERS Job No. 345-172 Sheet 1 of 24
 Subject FLOOD ROUTING THROUGH RESERVOIR By T. OTTJA Date 4-21-72
LIMESTONE COMMUNITY DAM Ckd. _____ Rev. _____

CAPACITY CURVE CALCULATIONS:

ELV.	AREA (mi. ²)	AREA (ACRE)	INCR. VOL. (AC-FT)	TOTAL VOL. (AC-FT)
513	0	0	0	0
530	0.02	12.8	725	725
540	0.08	51.2	320.0	3925
550	0.28	179.2	1152.0	15445



MAIN


Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 2 of 24
Subject LIMESTONE RESERVOIR By T. OTTAVIA Date 2-3-81
CAPACITY CURVE FITTING Ckd. _____ Rev. _____

```

      1          NCID          (CI)
      1          40 0000          525 5000
      2          72 5000          530 0000
      3          392 5000          540 0000
      ROW LOG REG CODE 3
SOURCE OF 98 48 F
TOTAL 2 98.2
REG 1 98.2 98.2 99.9
RESID 1 0.0 0.0
P SQUARE = 1.000


```

WHAT= 564 578+ 5 914,00 %

[illegible]

MAIN

Client CORPS OF ENGINEERS Job No. 64-72 Sheet 2 of 24
 Subject LIMESTONE DAM By CTD Date 2-2-2
SPILLWAY RATING CURVE Ckd. Rev.



Broad Crested Weir Formula,

$$Q = C \cdot L \cdot H^{3/2}$$


$$C \approx 3.0$$

$$L = 116$$

$$Q = 348 \cdot H^{3/2}$$

$$H = \frac{1}{(348)^{2/3}} \cdot Q^{2/3}$$

$$H = 0.021221655 \cdot Q^{2/3}$$



MAIN

Client CORDS & ENGINEERS Job No. 345-272 Sheet 7 of 11
 Subject LIMESTONE RESERVOIR By T. J. T. J. Date 2-2-21
FLOOD ROUTING CALCULATIONS Ckd. _____ Rev. _____

Drainage Area = 27.9 sq mi

For 17" runoff for 100-yr return $q_{PMF} = 350 \text{ cfs/sq mi}$

$$Q_{PMF} = 350 \times 27.9 = 9765 \text{ cfs.}$$

For this part of MAINE the Depth-Area-Duration curves yield a 13" of runoff. The Corps of Engineers New England Division also agrees that 13" of runoff should be used in the calculations.

In this case

$$\text{New } Q_{PMF} = 9765 \times \frac{13}{17} = 7477 \text{ cfs.}$$

The test flood is selected to be $\frac{1}{2}$ PMF for test calculation. The routing calculations are presented in the following pages

$$\text{Test Flood} = 7477 \times \frac{1}{2} = 3738 \text{ cfs.}$$

The flood routing calculations are presented in pages 5 and 6. As it can be seen from the results the flow is surging. A 10% reduction in the PMF is selected and the calculations are repeated (pages 7 and 8). The flood distribution (Fig. 1) is found to be almost equal to the original distribution.

MAIN

Client CORPS OF ENGINEERS Job No. 35-15 Sheet 4 of 24
 Subject LIMESTONE CRUMBLING SURVEILLANCE By TRW Date 1-1-71
225 CONTAINERS OBSERVATIONS Ckd. _____ Rev. _____

In order to estimate the scanning rate by overlapping the rating formula is altered to take care of scanning over the seam and through the material edges. The revision of the rating formula is presented in pages 9 and 10. The rating time is tabulated in page 11. The rating curve is illustrated in page 12.

The working calculations we found in case 13 and 14.

In view of the results presented in page 14 it is estimated that about 2.2 ft. overtopping will occur during test flood ($1/2$ P.M.F.).

MAIN

Client CORPS OF ENGINEERS Job No. 1345-272 Sheet 5 of 24
 Subject LIMESTONE RESERVOIR By T. D. OVA Date 2-3-81
FLOOD ROUTING CALCULATIONS Ckd. _____ Rev. _____

CALCULATIONS

ESTIMATING

EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES

These calculations are performed according to the Corps of Engineers Guidelines

LIMESTONE DAM

DRAINAGE AREA

$A = 27.9 \text{ (sq mi)}$

PEAK INFLOW
 $Q_{P1} = 12985 \text{ (cfs)}$

PRINCIPAL SPILLWAY CREST ELEV.
 $ELV1 = 526.5 \text{ (ft)}$

EMERGENCY SPILLWAY CREST ELEV.
 $ELV2 = 526.5 \text{ (ft)}$

Emergency Spillway Rating Curve is defined as:

$$H = a + Q^b$$

$$a = .0012211655$$

$$b = .66667$$

The Capacity - Elev. curve is defined as:

$$ELV = m + n + Log(\text{Volume})$$

$$m = 504.578$$

$$n = 5.914$$

TOTAL PMF RUNOFF
 $R = 13 \text{ (in)}$

STEP 1

Reduction of the OAI due to starting elevation at Principal Spillway Crest Elev.

Volume at 526.5 (ft)

$$\text{Volume1} = ELV1 - ELV2$$

$$\text{Volume1} = 40.04 \text{ (ac-ft)}$$

Volume at 526.5 (ft)

$$\text{Volume2} = ELV1 - ELV2$$

$$\text{Volume2} = 40.04 \text{ (ac-ft)}$$

Diff. of Volumes

$$\text{Diff Volume} = 0 \text{ (ac-ft)}$$

$$\text{Diff Volume} = 0 \text{ (ac-ft)}$$

$$\text{NEW } Q_{P1} = Q_{P1} + 1 - Q_{P1}$$

$$\text{NEW } Q_{P1} = 12985 \text{ (cfs)}$$

STEP 2

Surcharge Height

$$H = a + Q_{P1}^b$$

$$H = 11.66 \text{ (ft)}$$

Surcharge Volume

$$ELV = ELV2 + H$$

$$ELV = 538.16 \text{ (ft)}$$

$$\text{Volume} = 387.758 \text{ (ac-ft)}$$

$$\text{STOP1} = \text{Volume} - \text{Volume2}$$

$$347.717 \text{ (ac-ft)}$$

$$D-10 \text{ STOP1} = 16 \text{ (in)}$$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 6 of 24
 Subject LIMESTONE RESERVOIR By T. OTTAWA Date 2-3-81
FLOOD ROUTING CALCULATIONS Ckd. _____ Rev. _____

Corresponding Discharge:

$$Q_{P2} = Q_{P1} \times (1 - \text{STOR1} / R)$$

$$Q_{P2} = 12719 \text{ (cfs)}$$

$$\text{NEW STO. AVE.} = (\text{OLD STO. AVE.} + \text{STOR3}) / 2$$

$$\text{NEW STO. AVE.} = .16 \text{ (in.)}$$

S T E P 3

$$Q_{P4} = Q_{P1} \times (1 - \text{NEW STO. AVE.} / R)$$

$$Q_{P4} = 12722 \text{ (cfs)}$$

Surcharge Height:

Surcharge Height:

$$H = a \times Q_{P2} \wedge b$$

$$H = 11.56 \text{ (ft.)}$$

$$H4 = a \times Q_{P4} \wedge b$$

$$H4 = 11.56 \text{ (ft.)}$$

Surcharge Volume, STOR2:

$$E2 = H4 + H2$$

$$E2 = 538.06 \text{ (ft.)}$$

$$\text{ELW} = \text{ELW2} + H$$

$$\text{ELW} = 538.06 \text{ (ft.)}$$

$$\text{Volume} = 282.943 \text{ (ac-ft)}$$

C H E K I N G :

$$\text{Diff. Volume} = \text{Volume} - \text{Volume2}$$

$$\text{Diff. Volume} = 242.902 \text{ (ac-ft)}$$

or

$$\text{STOR2} = .16 \text{ (in.)}$$

$$E3 - E2 = 0 \text{ (ft.)}$$

$$\text{OLD STO. AVE.} = (\text{STOR1} + \text{STOR2}) / 2$$

$$\text{OLD STO. AVE.} = .16 \text{ (in.)}$$

R E S U L T S :

$$Q_{P3} = Q_{P1} \times (1 - \text{OLD STO. AVE.} / R)$$

$$Q_{P3} = 12721 \text{ (cfs)}$$

$$\text{AVERAGED DISCHARGE} = 12721 \text{ (cfs)}$$

$$\text{WATER SURFACE ELEV.} = 538.06 \text{ (ft.)}$$

$$\text{SURCHARGE HEIGHT} = 11.56 \text{ (ft.)}$$

S T E P 4

$$\text{CREST ELEV. OF THE DAM}$$

$$E_c = 534 \text{ (ft.)}$$

Surcharge Height:

$$\text{VOLUME AT DAM CREST ELEV}$$

$$V_c = 142.318 \text{ (ac-ft)}$$

$$H3 = a \times Q_{P3} \wedge b$$

$$H2 = 11.56 \text{ (ft.)}$$

VOLUME AT MAX. WATER SURFACE ELEV

$$V_w = 283.001 \text{ (ac-ft)}$$

Diff. Volume, STOR3:

$$E1 = H3 + H2$$

$$E1 = 538.06 \text{ (cfs)}$$

$$\text{Volume} = E1 \times (E1 - m) \times n$$

$$\text{Volume} = 282.989 \text{ (ac-ft)}$$

$$\text{STOR3} = \text{Volume} - \text{Volume2}$$

$$\text{STOR3} = 242.949 \text{ (ac-ft)}$$

or

$$\text{STOR3} = .16 \text{ (in.)}$$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 7 of 24
 Subject LIMESTONE RESERVOIR By T. OTUKA Date 2-3-81
FLOOD ROUTING CALCULATIONS Ckd. _____ Rev. _____

CALCULATIONS

ESTIMATING

EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES

These calculations are performed according to the Corps of Engineers Guidelines

LIMESTONE DAM

D A T A :

DRAINAGE AREA,
A = 27.9 (sq.mile)

PEAK INFLOW,
Q_{P1} = 6442 (cfs)

PRINCIPAL SPILLWAY CREST ELEV.,
ELV1 = 526.5 (ft)

EMERGENCY SPILLWAY CREST ELEV.,
ELV2 = 526.5 (ft)

Emergency Spillway Rating Curve is defined as,

$$H = a + Q^b$$

$$a = 0212311855$$

$$b = 66667$$

The Capacity - Elev. curve is defined as,

$$ELV = m + n \times \text{Log(Volume)}$$

$$m = 504.673$$

$$n = 5.914$$

TOTAL PMF RUNOFF,
R = 17 (in.)

S T E P 1

Reduction of the Elevation due to starting elevation at Principal Spillway Crest elev.

Volume at 526.5 (ft)

$$\text{Volume1} = \text{Excel}(\text{ELV1} - m) / n$$

$$\text{Volume1} = 40.04 \text{ (ac-ft)}$$

Volume at 526.5 (ft)

$$\text{Volume2} = \text{Excel}(\text{ELV2} - m) / n$$

$$\text{Volume2} = 40.04 \text{ (ac-ft)}$$

Diff. of Volumes,

$$\text{Diff. Volume} = 0 \text{ (ac-ft)}$$

or,

$$\text{Diff. Volume} = 0 \text{ (in.)}$$

$$\text{NEW } Q_{P1} = Q_{P1} \times (1 - D/R)$$

$$\text{NEW } Q_{P1} = 6442 \text{ (cfs)}$$

S T E P 2

Surcharge Height,

$$H = a + Q_{P1}^b$$

$$H = 7.34 \text{ (ft)}$$

Surcharge Volume,

$$\text{ELV} = \text{ELV2} + H$$

$$\text{ELV} = 533.84 \text{ (ft)}$$

$$\text{Volume} = 138.631 \text{ (ac-ft)}$$

$$\text{STOP1} = \text{Volume} - \text{Volume2}$$

$$\text{STOP1} = 98.59 \text{ (ac-ft)}$$

or,

$$\text{STOP1} = 06 \text{ (in.)}$$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-032 Sheet 8 of 24
 Subject LIMESTONE RESERVOIR By T. OTT Date 2-3-77
FLOOD ROUTING CALCULATIONS Ckd. _____ Rev. _____

Corresponding Discharge,

$$Q_{P3} = Q_{P1} * (1 - \text{STOR1} / R)$$

$$Q_{P3} = 6409 \text{ (cfs)}$$

$$\text{NEW STO. AVE.} = (\text{OLD STO. AVE.} + \text{TOR3}) / 2$$

$$\text{NEW STO. AVE.} = .06 \text{ (in.)}$$

S T E P 3

$$Q_{P4} = Q_{P1} * (1 - \text{NEW STO. AVE.} / R)$$

$$Q_{P4} = 6409 \text{ (cfs)}$$

Surcharge Height,

Surcharge Height

$$H = a * Q_{P3} ^ b$$

$$H = 7.32 \text{ (ft.)}$$

$$H_4 = a * Q_{P4} ^ b$$

$$H_4 = 7.32 \text{ (ft.)}$$

Surcharge Volume, STOR2,

$$E_2 = H_4 + H_2$$

$$E_2 = 533.92 \text{ (ft.)}$$

$$\text{ELW} = \text{ELW2} + H$$

$$\text{ELW} = 533.92 \text{ (ft.)}$$

$$\text{Volume} = 138.106 \text{ (ac-ft)}$$

C H E C K I N G :

$$E_3 - E_2 = 0 \text{ (ft.)}$$

$$\text{Diff. Volume} = \text{Volume} - \text{Volume2}$$

$$\text{Diff. Volume} = 98.065 \text{ (ac-ft)}$$

or

$$\text{STOR2} = .06 \text{ (in.)}$$

$$\text{OLD STO. AVE.} = (\text{STOR1} + \text{STOR2}) / 2$$

$$\text{OLD STO. AVE.} = .06 \text{ (in.)}$$

R E S U L T S :

$$Q_{P3} = Q_{P1} * (1 - \text{OLD STO. AVE.} / R)$$

$$Q_{P3} = 6409 \text{ (cfs)}$$

$$\text{AVERAGED DISCHARGE} = 6409 \text{ (cfs)}$$

$$\text{WATER SURFACE ELEV.} = 533.92 \text{ (ft.)}$$

S T E P 4

$$\text{SURCHARGE HEIGHT} = 7.32 \text{ (ft.)}$$

$$\text{CREST ELEV. OF THE DAM}$$

$$E_c = 534 \text{ (ft.)}$$

Surcharge Height

$$\text{VOLUME AT DAM CREST ELEV.}$$

$$V_c = 142.318 \text{ (ac-ft)}$$

$$H_3 = a * Q_{P3} ^ b$$

$$H_3 = 7.32 \text{ (ft.)}$$

$$\text{VOLUME AT MAX. WATER SURFACE ELEV.}$$

Diff. Volume, STOR3,

$$V_w = 138.106 \text{ (ac-ft)}$$

$$E_1 = H_3 + H_2$$

$$E_1 = 533.92 \text{ (cfs)}$$

$$\text{Volume} = E_{P3} * (E_1 - m) / n$$

$$\text{Volume} = 138.107 \text{ (ac-ft)}$$

$$\text{STOR3} = \text{Volume} - \text{Volume2}$$

$$\text{STOR3} = 98.067 \text{ (ac-ft)}$$


or

$$\text{STOR3} = .06 \text{ (in.)}$$

MAIN

Client CORP. OF ENGINEERS Job No. 345-742 Sheet 3 of 24
 Subject LIMESTONE COMMUNITY RES. By T. J. J. A. Date 2-9-74
FLOOD ROUTING Ckd. _____ Rev. _____

DETERMINATION OF THE OVERTOPPING



RATING FORMULA FOR THE SPILLWAY

$$Q_1 = C \times L \times H^{3/2}$$

$$Q_1 = 3.0 \times 116 \times H^{3/2} = 348 H^{3/2} \quad \text{--- (I)}$$

$$\text{or } H = \frac{1}{(348)^{2/3}} \times Q_1^{2/3}$$

$$H \approx 0.2202122 \times Q_1^{2/3} \quad \text{--- (II)}$$

RATING FORMULA FOR THE EMBANKMENTS

$$2 \times Q_2 = 2.9 \times 102 \times 2 \times H^{3/2}$$

$$2 \times Q_2 = 591.6 H^{3/2} \quad \text{--- (III)}$$

MAIN

Client CORPS OF ENGINEERS Job No. 345-172 Sheet 10 of 24
 Subject LIMESTONE COMMUNITY RESERVOIR By T. OTTO Date 2-2-21
FLOOD ROUTING Ckd. _____ Rev. _____

RATING FORMULA FOR THE SIDES

$$2 \times Q_3 = \frac{1.49 \times A \times R^{2/3} \times S^{1/2}}{m} \times 2$$

$$A = \frac{10 \times h \times h}{2} = 5h^2$$

$$P = [h^2 + (10h)^2]^{0.5} = h(1+10^2)^{0.5} \approx 10.05h$$

$$R = \frac{A}{P} = \frac{5h^2}{10.05h} = 0.4975 \times h$$

$$\left. \begin{array}{l} m = 0.07 \\ S = 0.04 \end{array} \right\} \text{30th estimated}$$

$$2 \times Q_3 = \frac{1.49 \times 5 \times h^2 \times (0.4975)^{2/3} \times h^{2/3} \times (0.04)^{0.5}}{0.07} \times 2$$

$$2 \times Q_3 = \frac{1.49 \times 5 \times (0.4975)^{1/3} \times (0.04)^{0.5} \times 2}{0.07} \times h^{8/3}$$

$$2 \times Q_3 \approx 26.73 \times h^{8/3} \quad \text{--- (IV)}$$

FOR THE CASE OF OVERTOPPING
 THE RATING FORMULA:

$$Q = Q_1 + 2Q_2 + 2Q_3 \quad L = h + 7.5$$

$$Q = 348 (h + 7.5)^{3/2} + 591.6 h^{3/2} + 26.73 h^{8/3}$$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 11 of 24
 Subject LIMESTONE COMMUNITY RESERVOIR By T. OTOVA Date 2-4-87
FLOOD ROUTING Ckd. _____ Rev. _____


RATING TABLE FOR WATER LEVELS ABOVE THE DAM

HEIGHT	DISCHARGE
0	7147
1	7300
2	7400
3	7500
4	7600
5	7700
6	7800
7	7900
8	8000
9	8100
10	8200
11	8300
12	8400
13	8500
14	8600
15	8700
16	8800
17	8900
18	9000
19	9100
20	9200
21	9300
22	9400
23	9500
24	9600
25	9700
26	9800
27	9900
28	10000
29	10100
30	10200
31	10300
32	10400
33	10500
34	10600
35	10700
36	10800
37	10900
38	11000
39	11100
40	11200
41	11300
42	11400
43	11500
44	11600
45	11700
46	11800
47	11900
48	12000
49	12100
50	12200
51	12300
52	12400
53	12500
54	12600
55	12700
56	12800
57	12900
58	13000
59	13100
60	13200
61	13300
62	13400
63	13500
64	13600
65	13700
66	13800
67	13900
68	14000
69	14100
70	14200
71	14300
72	14400
73	14500
74	14600
75	14700
76	14800
77	14900
78	15000
79	15100
80	15200
81	15300
82	15400
83	15500
84	15600
85	15700
86	15800
87	15900
88	16000
89	16100
90	16200
91	16300
92	16400
93	16500
94	16600
95	16700
96	16800
97	16900
98	17000
99	17100
100	17200

MAIN

Client COORP JE ENGINEERS Job No. 345-252 Sheet 12 of 24
 Subject LINESTONE COMMUNITY SEWER By J. S. J. A. Date 2-1-71
FLOOD FLOWING Ckd. Rev.

ELEV. RATING CURVE FOR OVERTOPPING CASE



OR,
 (1) $H = 0.000446 Q - 3.12$ (3) $H = 0.000246 Q - 1.55$
 (2) $H = 0.000358 Q - 2.31$ b-17 H = surcharge height (ft)

MAIN

Client CORPS OF ENGINEERS Job No 1345-072 Sheet 13 of 24
 Subject LIMESTONE COMMUNITY RESERVOIR By T. OTOLU Date 2-4-21
FLOOD ROUTING Ckd. _____ Rev. _____

ESTIMATING EFFECT OF SUPCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES

These calculations are performed according to the Corps of Engineers Guidelines

LIMESTONE DAM

O A T A :

DRAINAGE AREA,
 $A = 37.9$ (sq.mi.)

PEAK INFLOW,
 $Q_{p1} = 12885$ (cfs)

THE CREST ELV. OF THE DAM = 534
 (ft)

PRINCIPAL SPILLWAY CREST ELEV.,
 $ELV1 = 526.5$ (ft.)

EMERGENCY SPILLWAY CREST ELEV.,
 $ELV2 = 526.5$ (ft.)

Rating Curve is defined as :

$H = a1 * Q^{b1}$ (III) for before overtopping

$H = a1 * Q^{b1} + b1$ (III) for after overtopping

$a1 = .0202122$
 $b1 = .66667$

$a2 = .000446$
 $b2 = -3.12$

$a3 = .0003584$
 $b3 = -2.31$

$a4 = .000296$
 $b4 = -1.56$

Rating Curve Channel Discharges

$Q1 = 7147$
 $Q2 = 9242$
 $Q3 = 12032$

The Capacity - Elw curve is defined as:

$Elw = m + n * \log(\text{Volume})$

$m = 504.678$
 $n = 5.914$

TOTAL PMF RUNOFF,
 $R = 13$ (in.)

CALCULATIONS:

S T E P 1

Reduction of the Q_{p1} due to starting elevation at Principal Spillway crest elev.

Volume at 526.5 (ft.)

$\text{Volume1} = E_{xp}((ELV1 - m)/n)$
 $\text{Volume1} = 40.04$ (ac-ft)

Volume at 526.5 (ft.)

$\text{Volume2} = E_{xp}((ELV2 - m)/n)$
 $\text{Volume2} = 40.04$ (ac-ft)

Diff. of Volumes:

Diff. Volume = 0 (ac-ft)

or,

Diff. Volume, $D = 0$ (in.)

NEW $Q_{p1} = Q_{p1} * (1 - D/R)$

NEW $Q_{p1} = 12885$ (cfs)

MAIN

S T E P 4

Job No. 1345-072-017

By T.OTOVA

Client CORPS OF ENGINEERS
 Subject LIMESTONE RES. FLOOD ROUTING

Surcharge Height

Ckd. _____

From Formula (III)
 $H3 = 9.72$ (ft.)

Sheet 1a of 2aDate 2-4-81

Rev. _____

S T E P 2

Surcharge Height,

From Formula (III)
 $H = 9.75$ (ft.)

Surcharge Volume,

$ELW = ELW3 + H$
 $ELW = 536.25$ (ft.)

Volume = 208 343 (ac-ft)

STOR1 = Volume - Volume2

STOR1 = 168.303 (ac-ft)

or
 $STOR1 = .11$ (in.)

Corresponding Discharge,

$Qp2 = Qp1 * (1 - STOR1 / R)$
 $Qp2 = 12772$ (cfs)

S T E P 3

Surcharge Height,

From Formula (III)
 $H = 9.72$ (ft.)

Surcharge Volume, STOR2,

$ELW = ELW3 + H$
 $ELW = 536.22$ (ft.)

Volume = 207 177 (ac-ft)

Diff. Volume = Volume - Volume2

Diff. Volume = 167.137 (ac-ft)

or
 $STOR2 = .11$ (in.)

$OLD\ STOR\ AVE = (STOR1 + STOR2) / 2$

OLD STOR. AVE = .11 (in.)

$Qp3 = Qp1 * (1 - OLD\ STOR\ AVE / R)$

$Qp3 = 12773$ (cfs)

D-19

Diff. Volume, STOR3,

 $E1 = H3 + H2$ $E1 = 536.22$ (cfs)Volume = $Exp((E1 - m) / n)$

Volume = 207.181 (ac-ft)

STOR3 = Volume - Volume2

STOR3 = 167.141 (ac-ft)

or

STOR3 = .11 (in.)

$NEW\ STOR\ AVE = (OLD\ STOR\ AVE + STOR3) / 2$

NEW STOR. AVE = .11 (in.)

$Qp4 = Qp1 * (1 - NEW\ STOR\ AVE / R)$

$Qp4 = 12773$ (cfs)

Surcharge Height

From Formula (III)
 $H4 = 9.72$ (ft.)

 $E2 = H4 + H2$ $E2 = 536.22$ (ft.)

C H E C K I N G :

 $E3 - E2 = 0$ (ft.)

R E S U L T S :

AVERAGED DISCHARGE = 12773 (cfs)

WATER SURFACE ELEV = 536.22 (ft.)

SURCHARGE HEIGHT = 9.72 (ft.)

CREST ELEV. OF THE DAM
 $E_c = 534$ (ft.)

VOLUME AT DAM CREST ELEV.

$V_c = 142.318$ (ac-ft)

VOLUME AT MAX WATER SURFACE ELEV

$V_m = 207.182$ (ac-ft)

11 MAIN

Client CORPS OF ENGINEERS Job No. 1245-272 Sheet 15 of 24
 Subject LIMESTONE COMMUNITY DAM By T. TOVA Date 2-4-81
FAILURE ANALYSES Ckd. _____ Rev. _____

Determination of the prefailure depths and the submergence of the spillway due to failure discharges.

LIMESTONE DAM DAM FAILURE ANALYSES

These calculations are performed according to the RULE OF THUMB procedures of the Corps of Engineers.

The breach discharge:
 $Q_{b1} = 8/27 * W_b * a^{0.5} * Y_o^{3/2}$

Where,

Y_o is the height of the breach (from river bed to the max. pool level)

W_b is 35% of the length of the dam, or $W_b = 35 * W_d$

a is the acceleration of the area with (32.2 ft/sec^2)

$Y_o = 18 \text{ (ft)}$

$W_d = 320 \text{ (ft)}$

$W_b = 112 \text{ (ft)}$

From above equation:
 $Q_{b1} = 15595 \text{ (cfs)}$

The natural channel cross sections are simplified as triangular cross sections.

The stage-discharge relationship becomes as:

$h = [1.068 * n * \tan(\alpha) + 0.4 * 0.0001723 / 9.815]^{1/3/8}$

Where,

Q = Discharge (cfs)

α = Side slope angle (deg)

n = Channel slope

The cross section Area:

$A = h^2 / \tan(\alpha)$ (II)

The Volume of the Reservoir

$V = 143 \text{ (ac-ft)}$

or,

$V = 5185520 \text{ (cu-ft)}$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-077 Sheet 16 of 24
 Subject LIMESTONE DAM By T. OTOLA Date 2-4-21
FAILURE ANALYSES Ckd. _____ Rev. _____

PEACH C.B. CALCULATIONS

Test flood discharge:
 $Q_t = 7147 \text{ (cfs)}$

$z = 4 \text{ (deg.)}$
 $S = .004$
 $n = .07$
 $L = 10 \text{ (ft)}$

From Formula (I):

Prefailure height:

$h_1 = 10.9 \text{ (ft)}$

From Formula (II):

$A_1 = 1715 \text{ (sq-ft)}$

$Q = Q_{p1} + Q_t$

From Formula (I):

Total Height:
 $h = 16.9 \text{ (ft)}$

From Formula (II):

Total Area:
 $A = 4087 \text{ (sq-ft)}$

Residual Area:

$A_2 = A - A_1$

$A_2 = 2371 \text{ (sq-ft)}$

Residual Volume:

$V_1 = L \times A_2$

$V_1 = 23719 \text{ (cub-ft)}$

$Q_{p2} = Q_{p1} \times (1 - V_1 / V_2)$

$Q_{p2} = 15535 \text{ (cfs)}$

From Formula (I):

$Q = Q_{p2} + Q_t$

$Q = 22682 \text{ (cfs)}$

$h = 16 \text{ (ft)}$

From Formula (II):

$A = 4079 \text{ (ft)}$

Residual Area:

$A_2 = A - A_1$

$A_2 = 2363 \text{ (ft)}$

$V_2 = A_2 \times L$

$V_2 = 23639 \text{ (cub-ft)}$

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 23679 \text{ (cub-ft)}$

$Q_{p2} = Q_{p1} \times (1 - V_{ave} / V_2)$

$Q_{p2} = 15535 \text{ (cfs)}$

From Formula (I):

$Q = Q_{p2} + Q_t$

$h_2 = 16.8 \text{ (ft)}$

RESULTS

1. Prefailure Height = 10.9 (ft)

2. Postfailure Height = 16.8 (ft)

3. Breach Discharge = 15535 (cfs)

4. Reach Length = 10 (ft)

MAIN

Client CORPS OF ENGINEERS

Job No. 134C-072 Sheet 17 of 24

Subject LIMESTONE DAM

By T. OTOVA Date 2-4-81

FAILURE ANALYSES

Rev. Rev.

$$Q_{p2} = Q_{p1} * (1 - W1 / W)$$

$$Q_{p2} = 12567 \text{ (cfs)}$$

From Formula (I)

$$Q = Q_{p2} + Q_t$$

$$Q = 13714 \text{ (cfs)}$$

PRELIMINARY CALCULATIONS

Test flood discharge:
 $Q_t = 7147 \text{ (cfs)}$

$$\begin{aligned} s &= 4 \text{ (deg)} \\ S &= .004 \\ n &= .07 \\ L &= 500 \text{ (ft)} \end{aligned}$$

From Formula (I)

Prefailure height,

$$h_1 = 10.9 \text{ (ft)}$$

From Formula (II)

$$A_1 = 1715 \text{ (sq ft)}$$

$$Q = Q_{p1} + Q_t$$

From Formula (I)

Total Height,

$$h = 16.8 \text{ (ft)}$$

From Formula (II)

Total Area,

$$A = 4079 \text{ (sq ft)}$$

Residual Area,

$$A_2 = A - A_1$$

$$A_2 = 2363 \text{ (sq ft)}$$

Residual Volume,

$$W_1 = L * A_2$$

$$W_1 = 1181372 \text{ (cub-ft)}$$

$$h = 16 \text{ (ft)}$$

From Formula (III)

$$A = 7672 \text{ (ft)}$$

Residual Area,

$$A_2 = A - A_1$$

$$A_2 = 1956 \text{ (ft)}$$

$$W_2 = A_2 * L$$

$$W_2 = 978277 \text{ (cub-ft)}$$

$$Wave = (W_1 + W_2) / 2$$

$$Wave = 1080124 \text{ (cub-ft)}$$

$$Q_{p2} = Q_{p1} * (1 - Wave / W)$$

$$Q_{p2} = 12827 \text{ (cfs)}$$

From Formula (I)

$$Q = Q_{p2} + Q_t$$

$$h_2 = 16.1 \text{ (ft)}$$

RESULTS

1. Prefailure Height = 10.9 (ft)

2. Postfailure Height = 16.1 (ft)

3. Breach Discharge = 12827 (cfs)

4. Beach Length = 500 (ft)

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 18 of 24
 Subject LIMESTONE DAM By T. OTTAVIA Date 2-4-81
FAILURE ANALYSIS Ckd. _____ Rev. _____

$$Q_{P2} = Q_{P1} * (1 - V1 / V)$$

$$Q_{P2} = 10757 \text{ (cfs)}$$

From Formula (I),

$$Q = Q_{P2} + Q_t$$

$$Q = 17904 \text{ (cfs)}$$

R E A C H (2) CALCULATIONS

Test flood discharge:
 $Q_t = 7147 \text{ (cfs)}$

$$\begin{aligned} a &= 4 \text{ (deg.)} \\ S &= .004 \\ n &= .07 \\ L &= 500 \text{ (ft)} \end{aligned}$$

From Formula (I),

Prefailure height,

$$h_1 = 10.9 \text{ (ft)}$$

From Formula (II),

$$A_1 = 1715 \text{ (sq. ft.)}$$

$$Q = Q_{P1} + Q_t$$

From Formula (I),

Total Height,
 $h = 15.1 \text{ (ft)}$

From Formula (II),

$$\begin{aligned} \text{Total Area,} \\ A &= 3707 \text{ (sq-ft)} \end{aligned}$$

Residual Area,

$$\begin{aligned} A_2 &= A - A_1 \\ A_2 &= 1992 \text{ (sq-ft)} \end{aligned}$$

Residual Volume,

$$V_1 = L * A_1$$

$$V_1 = 996117 \text{ (cub-ft)}$$

$$h = 15 \text{ (ft)}$$

From Formula (II),

$$A = 3416 \text{ (ft)}$$

Residual Area,

$$A_2 = A - A_1$$

$$A_2 = 1700 \text{ (ft)}$$

$$V_2 = A_2 * L$$

$$V_2 = 850390 \text{ (cub-ft)}$$

$$V_{ave} = (V_1 + V_2) / 2$$

$$V_{ave} = 923253 \text{ (cub-ft)}$$

$$Q_{P2} = Q_{P1} * (1 - V_{ave} / V)$$

$$Q_{P2} = 10909 \text{ (cfs)}$$

From Formula (I),

$$Q = Q_{P2} + Q_t$$

$$h_2 = 15.5 \text{ (ft)}$$

RESULTS

$$1 \text{) Prefailure Height} = 10.9 \text{ (ft)}$$

$$2 \text{) Postfailure Height} = 15.5 \text{ (ft)}$$

$$3 \text{) Breach Discharge} = 10909 \text{ (cfs)}$$

$$4 \text{) Reach Length} = 500 \text{ ft}$$

11 **MAIN**

Client CORPS OF ENGINEERS Job No. 1345-D-2 Sheet 19 of 24
 Subject LIMESTONE DAM By T. STORV Date 2-5-21
FAILURE ANALYSES Ckd. _____ Rev. _____

Determination of the downstream flood levels by considering the reduction of the spillway discharge due to submergence effects.

"Ref. Design of Small Dams, p.p. 380 figure 252, 1948."

$$H_e = 7.5 \text{ ft} \quad h_d = 14 - 16.8 - 2.7 \text{ ft.} \quad h_d/H_e = 0.29$$

$$\frac{h_d + H_e}{H_e} = \frac{14}{7.5} = 2.53$$

Reduction = 6 percent

$$Q_E = 7147 - 0.294 = 6718 \text{ cfs.}$$

LIMESTONE DAM
 DAM FAILURE ANALYSES

From above equation,
 $Q_{P1} = 15595 \text{ cfs.}$

These calculations are performed according to the RULE OF THUMB procedures of the Corps of Engineers

The natural channel cross sections are simulated as triangular cross sections

The breach discharge
 $Q_{P1} = 8/27 \times W_b \times \sqrt{g} \times H_e^{3/2}$

The stage-discharge relationship becomes as

Where,

$$h = [1.066 + n + \tan^2 \alpha] \times 0.4 \times 0.013 \times 2/3 \times 8/5 \times 3/8 \times 1.1$$

H_e is the height of the breach from river bed to the main pool level.

Where

W_b is 75% of the length of the dam, or $W_b = 35 \times W_d$

Q = Discharge (cfs.)
 α = Side slope angle (degrees)
 β = Channel slope

g is the acceleration of the earth with (32.2 ft/sec^2)

The cross section Area

$$A = h^2 / 2 \times \tan^2 \alpha \times 1.1$$

$$H_e = 19 \text{ ft.}$$

$$W_b = 320 \text{ ft.}$$

$$W_d = 112 \text{ ft.}$$

The Volume of the Reservoir

$$V = 142 \text{ acre-ft.}$$

or

$$V = 8135520 \text{ cu. ft.}$$

ADA156 277

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
LIMESTONE DAM (ME 004..1U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 81

22


UNCLASSIFIED

F/G 13/13

NL



END DATE FILMED 8-85	END DATE FILMED 8-85
-------------------------------	-------------------------------



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

MAIN

Client CORPS OF ENGINEERS Job No. 1345-D72 Sheet 20 of 24
 Subject LIMESTONE DAM By T. OTOVA Date 2-5-81
FAILURE ANALYSIS Ctd. Rev.

$$Q_{P2} = Q_{P1} * (1 - V_1 / V)$$

$$Q_{P2} = 12580 \text{ (cfs)}$$

From Formula (I),

$$Q = Q_{P2} + Q_t$$

$$Q = 19298 \text{ (cfs)}$$

$$h = 15 \text{ (ft)}$$

From Formula (II),

$$A = 3613 \text{ (ft)}$$

Residual Area,

$$A_2 = A - A_1$$

$$A_2 = 1976 \text{ (ft)}$$

$$V_2 = A_2 * L$$

$$V_2 = 988064 \text{ (cub-ft)}$$

$$V_{ave} = (V_1 + V_2) / 2$$

$$V_{ave} = 1091997 \text{ (cub-ft)}$$

$$Q_{P2} = Q_{P1} * (1 - V_{ave} / V)$$

$$Q_{P2} = 12842 \text{ (cfs)}$$

From Formula (I),

$$Q = Q_{P2} + Q_t$$

$$h_2 = 15.9 \text{ (ft)}$$

RESULTS

1.) Prefailure Height = 10.7 (ft)

2.) Postfailure Height = 15.9 (ft)

3.) Breach Discharge = 12842 (cfs)

p-25 4.) Reach Length = 500 (ft)

REACH (1) CALCULATIONS

Test flood discharge:

$$Q_t = 6718 \text{ (cfs)}$$

$$a = 4 \text{ (deg.)}$$

$$S = .004$$

$$n = .07$$

$$L = 500 \text{ (ft)}$$

From Formula (I),

Prefailure height,

$$h_1 = 10.7 \text{ (ft)}$$

From Formula (II),

$$A_1 = 1637 \text{ (sq-ft)}$$

$$Q = Q_{P1} + Q_t$$

From Formula (I),

Total Height,

$$h = 16.7 \text{ (ft)}$$

From Formula (II),

Total Area,

$$A = 4029 \text{ (sq-ft)}$$

Residual Area,

$$A_2 = A - A_1$$

$$A_2 = 2391 \text{ (sq-ft)}$$

Residual Volume,

$$V_1 = L * A_2$$

$$V_1 = 1195930 \text{ (cub-ft)}$$

MAIN

Client CORP OF ENGINEERS Job No. 1345-032 Sheet 21 of 24
 Subject LIMESTONE DAM By T. O. FLYNN Date 2-5-81
FAILURE ANALYSIS Cld. _____ Rev. _____

$$Qp2 = Qp1 * (1 - V1 / V)$$

$$Qp2 = 10752 \text{ (cfs)}$$

From Formula (I),

$$Q = Qp2 + Qt$$

$$Q = 17470 \text{ (cfs)}$$

$$h = 15 \text{ (ft)}$$

From Formula (II),

$$A = 3354 \text{ (ft)}$$

Residual Area,

$$A2 = A - A1$$

$$A2 = 1716 \text{ (ft)}$$

$$V2 = A2 * L$$

$$V2 = 858142 \text{ (cub-ft)}$$

$$Vave = (V1 + V2) / 2$$

$$Vave = 932289 \text{ (cub-ft)}$$

$$Qp2 = Qp1 * (1 - Vave / V)$$

$$Qp2 = 10906 \text{ (cfs)}$$

From Formula (I),

$$Q = Qp2 + Qt$$

$$h2 = 15.3 \text{ (ft)}$$

RESULTS :

1.) Prefailure Height = 10.7 (ft)

2.) Postfailure Height = 15.3 (ft)

3.) Breach Discharge = 10906 (cfs)

D-26 4.) Reach Length = 500 (ft)

PEACH (2) CALCULATIONS

Test flood discharge:
 $Qt = 6718 \text{ (cfs)}$

$$\theta = 4 \text{ (deg.)}$$

$$S = .004$$

$$n = .07$$

$$L = 500 \text{ (ft)}$$

From Formula (I),

Prefailure height,

$$h1 = 10.7 \text{ (ft)}$$

From Formula (II),

$$A1 = 1637 \text{ (sq-ft)}$$

$$Q = Qp1 + Qt$$

From Formula (I),

Total Height,

$$h = 15.9 \text{ (ft)}$$

From Formula (II),

Total Area,

$$A = 3650 \text{ (sq-ft)}$$

Residual Area,

$$A2 = A - A1$$

$$A2 = 2012 \text{ (sq-ft)}$$

Residual Volume,

$$V1 = L * A2$$

$$V1 = 1006436 \text{ (cub-ft)}$$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-177 Sheet 22 of 24
 Subject LIMESTONE DAM By T. OTOVA Date 2-5-81
FAILURE ANALYSES Ctd. _____ Rev. _____

Determination of the downstream flood levels due to failure of the dam in dry conditions ($Q_{test} = 0$ cfs)

LIMESTONE DAM DAM FAILURE ANALYSES

These calculations are performed according to the RULE OF THUMB procedures of the Corps of Engineers

The breach discharge:
 $Q_{b1} = 8/27 * W_b * a^{0.5} * Y_o^{3/2}$

Where,

Y_o is the height of the breach (from river bed to the max. pool level)

W_b is 35% of the length of the dam, or $W_b = .35 * W_d$

a is the acceleration of the gravity (32.2 ft/sec²)

$$Y_o = 11.5 \text{ (ft)}$$

$$W_d = 170 \text{ (ft)}$$

$$W_b = 59 \text{ (ft)}$$

From above equation,
 $Q_{b1} = 3901 \text{ (cfs)}$

The natural channel cross sections are simplified as triangular cross sections

The stage-discharge relationship becomes as,

$$h = [1.068 * n * \tan(a) * Q / C \cos(a)^{2/3} / S^{1/3}]^{3/8} \dots (I)$$

Where,

Q = Discharge (cfs)
 a = Side slope angle (deg)
 S = Channel slope

The cross section Area:

$$A = h^2 / \tan(a) \dots (II)$$

The Volume of the Reservoir:

$$V = 40 \text{ (ac-ft)}$$

or
 $V = 1742400 \text{ (cub-ft)}$

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 23 of 24
 Subject LIMESTONE DAM By T. OTUJA Date 2-5-81
FAILURE ANALYSES Ctd. _____ Rev. _____

REACH (1) CALCULATIONS

Test flood discharge:
 $Q_t = 0$ (cfs)

$z = 4$ (deg.)
 $S = .004$
 $n = .07$
 $L = 500$ (ft)

From Formula (I),

Prefailure height,

$h_1 = 0$ (ft)

From Formula (II),

$A_1 = 0$ (sq-ft)

$Q = Q_{p1} + Q_t$

From Formula (I),
 Total Height,
 $h = 8.7$ (ft)

From Formula (II),
 Total Area,
 $A = 1089$ (sq-ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 1089$ (sq-ft)

Residual Volume,

$V_1 = L \times A_2$

$V_1 = 544793$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - V_1 / V)$

$Q_{p2} = 2681$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$Q = 2681$ (cfs)

$h = 7$ (ft)

From Formula (II),

$A = 822$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 822$ (ft)

$V_2 = A_2 \times L$

$V_2 = 411250$ (cub-ft)

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 478021$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - V_{ave} / V)$

$Q_{p2} = 2681$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$h_2 = 7.7$ (ft)

RESULTS :

1. Prefailure Height = 0 (ft)

2. Postfailure Height = 7.7 (ft)

3. Breach Discharge = 2681 (cfs)

4. Reach Length = 500 (ft)

MAIN

Client CORPS OF ENGINEERS Job No. 1345-077 Sheet 24 of 24
 Subject LIMESTONE DAM By T. OTOVA Date 2-5-81
FAILURE ANALYSES Ctd. _____ Rev. _____

REACH (2) CALCULATIONS

Test flood discharge:
 $Q_t = 0$ (cfs)

$s = 4$ (deg.)
 $S = .004$
 $n = .07$
 $L = 500$ (ft)

From Formula (I),

Prefailure height,

$h_1 = 0$ (ft)

From Formula (II),

$A_1 = 0$ (sq-ft)

$Q = Q_{p1} + Q_t$

From Formula (I),
 Total Height,
 $h = 7.7$ (ft)

From Formula (II),
 Total Area,
 $A = 856$ (sq-ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 856$ (sq-ft)

Residual Volume,

$V_1 = L \times A_2$

$V_1 = 428329$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - V_1 / V)$

$Q_{p2} = 2135$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$Q = 2135$ (cfs)

$h = 6$ (ft)

From Formula (II),

$A = 693$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 693$ (ft)

$V_2 = A_2 \times L$

$V_2 = 346642$ (cub-ft)

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 387486$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - V_{ave} / V)$

$Q_{p2} = 2201$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$h_2 = 7$ (ft)

RESULTS :

- 1.) Prefailure Height = 0 (ft)
- 2.) Postfailure Height = 7 (ft)
- 3.) Breach Discharge = 2201 (cfs)
- 4.) Reach Length = 500 (ft)

APPENDIX E

"NATIONAL INVENTORY OF DAMS IN THE UNITED STATES"

PART III - INVENTORY OF DAMS IN THE UNITED STATES SUPPLEMENTARY DATA

IDENTITY
NUMBER

STATE

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

LOCATION	TOWN	M.E.D. PERMIT NO.	STATE NUMBER	F.E.R.C. NO.	U.S.S. SHEET
	LIMESTONE				

DRAINAGE CHARACTERISTICS	DRAINAGE AREA SQ. MI.	FLOW DATA			CREST ELEV. M.S.L.	ABUT. ELEV. M.S.L.	USABLE STORAGE ACRES FEET	RESERVOIR AREA ACRES	FLASH BOARD FT.	OUTLET CONDUITS NO.	INVERT ELEV. M.S.L.
		MIN. C.F.S.	AVE. C.F.S.	MAX. C.F.S.							
	2.8	1.0	1.0	1.0	52.5	53.0	4.0	1.0	1.0	1.0	52.5

POWER DATA	GENERATION UNITS				AVERAGE ANNUAL GENERATION K.W.H.				LAST GEN. YEAR	RETIRED YEAR	FORMER USE	CAPACITY FACTOR
	INSTALLED NO.	INSTALLED K.W.	PLANNED NO.	PLANNED K.W.								
	1	1.0	1	1.0	1.0	1.0	1.0	1.0	1950	1950		

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

NEL FORM 1 JAN 79 80 (TEST)

 PART II - INVENTORY OF DAMS IN THE UNITED STATES (PURSUANT TO PUBLIC LAW 92-367)										FORM APPROVED OMB NO. 48-80421 REQUIREMENTS CONTROL SYMBOL DAM-CWE-17		IDENTITY NUMBER	
										STATE		1 2 3 4 5 6 7	
										ME		00492	

See reverse side for instructions.


[29]		[30]		[31]		[32]		[33]		[34]		[35]		[36]		[37]		[38]		[39]		[40]		[41]		[42]		[43]		[44]		[45]	
STATISTICS		CREST LENGTH (ft)		SPILLWAY		MAXIMUM DISCHARGE (cfs)		VOLUME OF DAM (CY)		POWER CAPACITY		NAVIGATION LOCKS		BLANK																			
29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60		
2	3	0	0	4	1	1	6	7	5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		

[46]		[47]		[48]	
OWNER		ENGINEERING BY		CONSTRUCTION BY	
TOWN OF LIMESTONE		EDWARD C JORDAN		EDWARD C JORDAN CO, INC	

[49]		[50]		[51]		[52]	
REGULATORY AGENCY		CONSTRUCTION		OPERATION		MAINTENANCE	
NONE		NONE		NONE		NONE	

[53]		[54]		[55]	
INSPECTION BY		INSPECTION DATE		AUTHORITY FOR INSPECTION	
		DAY MO YR			

[56]	
REMARKS	
34-ESTIMATED	

 PART I - INVENTORY OF DAMS IN THE UNITED STATES (PURSUANT TO PUBLIC LAW 92-367)										FORM APPROVED OMB NO. 49-10421 REQUIREMENTS CONTROL SYMBOL DAM-CR-17		IDENTITY NUMBER STATE	
See reverse side for instructions										ME 00492		ME 00492	

[12] [13] [14] [15] [16] [17] [18]										[19]		[110] [111]		[112]	
IDENTIFICATION										NAME		LATITUDE (North)		REPORT DATE	
DIVISION	STATE	COUNTY	COUNTY	CONGR	CONGR	STATE	COUNTY	CONGR	CONGR						
NE	ME	00	03	02	XX	XX	XX	XX	XX	LIMESTONE COMMUNITY DAM		46 45 8 67 49 51 7 FEB 8 10			

[133]										[134]	
IDENTIFICATION (Continued)										NAME OF IMPONDMENT	
POPULAR NAME											
SAME										LIMESTONE COMMUNITY POND	

[135] [136]										[137]		[138]		[139]		[140]	
LOCATION										RIVER OR STREAM		NEAREST DOWNSTREAM CITY - TOWN - VILLAGE		DIST FROM DAM (mi)		POPULATION	
0101 LIMESTONE STREAM										LIMESTONE		LIMESTONE		0		104902	

[21]										[22]		[23]		[24]		[25]		[26]		[27]		[27A]		[27F]			
STATISTICS										TYPE OF DAM		YEAR COMPLETED		PURPOSES		STRUCTURAL HEIGHT (ft)		HYDRAULIC HEIGHT (ft)		IMPONDING CAPACITIES		CORPS BRIG DIST.		VERIFICATION DATE		BLANK	
RE										1978		CR		19		19		142		40		NNNN					

[28]									
REMARKS									

END

DATE
FILMED

8 - 85

END

DATE
FILMED

8 - 85

DT